

OCT 06 1997

COMMISSION

LIBER 2 PAGE 167

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft Township

KALAMAZOO

(County)

Located In:

Corner Code #

1. Public Land Survey	T 4S R 11W	M-05
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

CLERK - REGISTER

*Janice Brown*

97 JUL 29 AM 11 01

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on May 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; Set Post, Corner to Sections 12 & 13  
White Oak 13" South 28° West 64 Lks  
White Oak 18" 94 Lks

1889: F. Hodgman, County Sureyor; "Set post in place of stake and stone of former survey. No tree near."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1946: Wilkins and Wheaton Engineering Company; found tile 12" down at end of fence to West, 6.6' South of fence to East.

1992: Wilkins and Wheaton Engineering Company; found tile down about 4".

1997: Found tile with sleeve down about 4", 211'± West of old railroad bed.

*R.E.S.*  
**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 6-19-1997

M-05 Southeast Corner Section 12, T. 4 S., R. 11 W.; ratified by the Kalamazoo County Remonumentation Program Peer Group on June 19, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found a 3" round tile as placed in 1889 by F. Hodgman in a remonumentation survey. A remonumentation sleeve was over tile.  
Exist. Nail/Tab over PK Nail/Tab on East Side Power Pole North 05°-30' East 35.94'  
Exist. PK Nail/Tab on South Side Power Pole North 77°-30' East 210.98'  
Exist. Nail/Tab on South Side Guy Pole North 88°-24' East 205.22'  
PK Nail in East Side 8" Maple (Nursery) North 19°-50' West 21.00'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 7-29-97