

FEB 08 1999

SECTION

LIBER

2 PAGE 389

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SCHOOLCRAFT TWP KALAMAZOO (County) Located In: Corner Code #

Table with 4 columns: Item, T, R, Corner Code #. Row 1: Public Land Survey, T 4S, R 11W, M-11. Row 2: Property Controlling in Section, S, T, R. Row 3: Miscellaneous Property in Section, S, T, R.

- 4. Lot No. , Recorded Plat
5. Private Claims
6. IWM Job No. 28528

I, Allen H. McMachen, in a field survey on November 5, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - Robert Clark Jr., D.S., "Set post corner to Secs 25 & 36", Hickory 5" S. 15 1/2" W. 60 lks., D.O. N. 67" W. 64 lks..
1899 - F. Hodgman, C.S., "Found stone with brick around 66 lks. North of corner of Sections 30 & 31 Brady, set post, witness. Wh. Oak 20" S. 61 1/2" W. 95 lks., Maple 12" S. 19 1/2" W. 115 lks..
1922 - Kalamazoo County Rd. Comm., Placed iron rod 'near' Sec. cor. for road alignment, shows dimension from "tile" at NE cor., Sec. 25 to P.I. iron near S.E. cor., Sec. 25 @ 5316.9' and from said P.I. iron to "tile" at W 1/4 cor., Sec. 36 @ 2647.8'.
1949 - Wilkins & Wheaton, Measured from "tile" at NE cor., Sec 25 South 2655.3' to "tile" at E 1/4 cor., Sec. 25.
1957 - W.D. Ingersoll, R.L.S., Finds iron rod (previously placed by Road Commission) and holds for Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box in centerline 24th Street and centerline "Y" Avenue to West. Dug below and found second iron directly below the first one at 2.3' below surface, continued digging to depth of 4.5 feet and found no additional evidence of corner. Measured North from iron in box 5317.7 feet to N.E. corner, Sec. 25 and realized iron in box was the iron placed in 1922 for road alignment. To establish corner location, measured from the N.E. cor., Sec. 25 (being an iron in box 4.62' South of found stone at N.W. cor., Sec. 30, Brady Twp.) South to a "found tile" at the E 1/4 cor., Sec. 36, Schoolcraft Twp. at 7965.98 feet (1922 Road Commission = 7964.7'). Divided dimension into 3 equal half miles (7965.98/3 = 2655.33') and ran a straight line between Sec. cors. 1 1/2 miles apart to establish a search area (being 5310.66 feet South of N.E. cor., Sec. 25). Dug at said position and found a semi-circle of brick 30" below road surface but did not recover tile. Center of brick was at point set for center of search area. Center of brick is also very near (±0.5') the Easterly extension of a line between N.W. cor. Sec. 36 (Std. marker over tile) and the N 1/4 corner, Sec. 36 (Std marker over tile). Found semi-circle of brick was found to 7.5' North and 1' West of fd. iron in box (1922 Road Commission iron).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The center of brick circle found is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument in center of found brick (position being on line with NE cor., Sec. 25 and the E 1/4 cor., Sec. 36 and being 2655.33 feet North of E 1/4 cor., Sec. 36) and placed monument box over Harrison Monument. Accessories:

- Nail & Tab in 24" Maple N. 50° W. 80.30'
Nail & Tab in 8" Cedar S. 70° W. 77.84'
Nail & Tab in 20" Oak S. 80° E. 92.16'
Nail & Tab in U. Pole S. 75° E. 52.16'

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 12-18-1997



Signed by Allen H. McMachen Date 12/15/98
Surveyor's Michigan License No. 16935

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD '98 DEC 15 PM 3 50 CLERK - REGISTER

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. Contains numbers 6-36 in a grid pattern.