

SURVEY & REMONUMENTATION

AUG 06 1996
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 016

For corners in Kalamazoo (County) Located In: _____ Corner Code # _____
Schoolcraft Twp.

1. Public Land Survey	T 4 S. R 11 W.	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
96 MAY 23 PM 1 48
Register of Deeds Stamp & File Number

CLERK - REGISTER

I, Robert E. Snell, in a field survey on March 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set East 1/4 post Section 36.

- B1. Oak 5" S. 37 1/2° W. 10 lks.
- B1. Oak 6" N. 35 1/2° W. 25 lks.

1889: F. Hodgman, County Surveyor; found stone with brick, glass and broken crockery around, set post.

- Burr Oak 16" N. 24° E. 65 1/2 lks.
- Burr Oak 16" N. 29 1/2° W. 78 lks.
- Maple 12" S. 33 3/4° W. 72 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1972: Allen H. McMachen, R.L.S. #16985; L.C.R.C. Liber 1, Page 223, found tile with cross in top. Set monument box over.

- 18" Maple West 33.14'
- 12" Elm S. 40° E. 51.36'

1996: Found 1/2" x 12" iron bar over tile 20" deep in monument box.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-18-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12: East 1/4 post of Section 36, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with cross on top as set by F. Hodgman, County Surveyor in a remonumentation survey in 1889. Set 18" of 20" Harrison Monument in concrete over tile in monument box.

- PK Nail on North Side of 13" Maple N. 42° E. 57.07'
- PK Nail on North Side of 30" Elm S. 30° E. 50.64'
- PK Nail on North Side of 8" Hickory S. 60° W. 41.97'
- Nail & Tab on North Side of 22" Hickory N. 70° W. 31.35'

Signed by Robert E. Snell Date 5-23-96

Surveyor's Michigan License No. 9734