

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

DEC 18 PM 2 28

For corners in

Kalamazoo (County) Located in: Corner Code #

1. Public Land Survey T 4 S. R 12 W. A4  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. N/A, Recorded Plat N/A

5. Private Claims

*James D. Young*  
CLERK-REGISTER

LIBER 1 1417

Register of Deeds Stamp & File Number

I, GREGORY N. JENSEN, in a field survey on 07/17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A4 WEST 1/4 POST SEC. 7, T.4 S., R.12 W.
- HODGEMAN - FOUND STONE FOR 1/4 CORNER IN TOWNSHIP WEST. SET STONE WITH DRILL HOLE 33 1/2 LKS (22.11'). NORTH (WITNESS TO PORTER CORNER) AND SIDE STONES 50 LKS (33') EAST AND WEST.
  - STRONG - STONE AND CROCKERY BISECTED WEST LINE OF THE SECTION AS NO ONE KNOWS THAT THE WELL SCREEN (AT E. 1/4 SEC. 12, T.4 S., R.13 W., PORTER TOWNSHIP) WAS CORRECT.  
STONE-TIN AND GLASS ON BISECTION  
BLACK WALNUT 8", S 45° E. 60 1/2 LKS. (39.39)  
APPLE 6", N 50° E. 38 LKS. (25')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A4 WEST 1/4 POST SEC. 7, T.4 S., R.12 W.

FOUND A STONE 2' UNDER PAVEMENT ON TOWNLINE 3' WEST OF TRAVELED CENTER LINE OF VAN KAL AVE. ON BISECTION OF WEST LINE SEC. 7 PER ED STRONG FEB. 21, 1906. STONE ALSO INTERSECTS PROJECTION OF A FOUND WELL POINT C 1/4 OVER A FOUND WELL POINT WEST 1/3 COR.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
11-16-95  
*R.E.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A4 WEST 1/4 POST SEC. 7, T.4 S., R.12 W. RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PROGRAM PEER GROUP ON NOVEMBER 16 1995. PLACED HARRISON IN MONUMENT BOX OVER STONE IRON AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

- TOP POINT LARGE BOULDER, S. 45° W - 30.65'
- TEL. POLE, N 30° W. - 53.30'
- 14" WALNUT, N 35° E. - 65.4'
- EAST 1/4 POST SEC. 12, T.4 S., R.13 W GALVANIZED 1" DIA. ROD SOUTH 22.11'

Signed by *Gregory N. Jensen*  
Surveyor's Michigan License No. 31593

Date 12/18/95

