

SURVEY & REMONUMENTATION

APR 27 1995

LIBER 1 PG 1198

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

Prairie Ronde

1. Public Land Survey

T 4 S R 12 W

A-7

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 DEC 9 AM 9 24
CLERK - REGISTER

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 19, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829: U.S. Government Survey; Enter West boundary, 36 Lks North of Post. Set Post at intersection to Corner of Sections 18 and 19.

Beech 24" North 21° East 38 Lks
Beach 9" South 72° East 19 Lks

1872: S. Hodgeman, County Surveyor; Section Corner, found stake hole and set large stone with drill hole.

1894: E. Strong, County Surveyor; Found stone at Southwest Corner.

Elm 12" South 60°± East 66½ Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994; Found at the surface, 1/2" x 18" Capped Iron (J.Hunt); further digging revealed a drilled stone (12" diameter and 18" long), 1.5' South of iron.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-15-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Southwest Corner Section 18, T. 4 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found drilled stone as called for in survey by S. Hodgeman in 1872 and is accepted as a careful and faithful perpetuation of the original corner's position. Lowered stone and placed a 20" Harrison monument over with a monument box over stone.

Existing 60d Spike in East Side Power Pole N 40° W 95.14'
Existing Nail/Tab in East Side Power Pole N 28° E 69.58'
PK Nail in West Side 18" Elm N 80° E 114.60'
PK Nail in North Side Power Pole S 58° E 129.74'
CL "W" Ave S 2.75'

S. 23.87' to Section Corner Porter Township

Signed by

Robert E. Snell

Date

12-9-94

Surveyor's Michigan License No.

9734