

APR 07 1996

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'95 DEC 14 PM 3 30

S.W. cor. Sec. 31
COMMISSION LAND CORNER RECORDATION CERTIFICATE

Prairie Ronde Township Filing Requirement of Act 74, Mich. P.A. 1970
For corners in Kalamazoo Located In: Corner Code #
(County)

- 1. Public Land Survey T 4S. R 12W. A-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

James Young
CLERK-REGISTER
LIBER **1 1407**
Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on December 22, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - William Brookfield, D.S. Set post (for survey of Porter Township)
- 1875 - F. Hodgman, Found stake and stones set on former survey correct
- 1876 - Norman S. Andrews, C.S. (St. Joseph Co.), found stakes from original survey, measured SOUTH 12.955 ch. (855.03') and continued SOUTH 19.915 ch. (1314.39') to 1/4 post for a total of 32.87 ch. (2169.42')
- 1884 - A.A. Fosdick, C.S. (Van Buren Co.), found corner, old witness trees remain or stumps of them, new ones made, wits: 12" Elm S. 09° W. 145.5 lks. (96.03') meas. West 19.955 ch. (1317.03') to 1/8 post & continued West 19.955 ch. (1317.03') to 1/4 post for a total of 2634.06'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Dia. Well point in center of ring of stones, said stones were found in muck soil. Also found remnants of old wood stake next to well point 2' below surface. Measured South 2170' to tree line to East no corner found, (1876 meas. 2169.42') measured West 2634' to fence line to North, no corner found (1884 meas. 2634.06') said well point was approved and authorized by the Van Buren County Remonumentation Peer Group on May 11, 1994.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-20-95**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 2" dia. well point is accepted as a careful and faithful perpetuation of the original corner. Removed well point and placed standard Van Buren County Section Corner monument and mon. box over, Accessories:

- Nail & Tab in Utility Pole N. 55° E. 71.10'
- Nail & Tab in Utility Pole S. 80° W. 117.55'
- Nail & Tab in 24" Maple N. 60° W. 76.15'
- Nail & Tab in 36" Oak S. 20° W. 110.49'



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 12/13/95