

1 APR 01 1996
2 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'95 DEC 18 PM 2 28

For corners in

Kalamazoo (County) Located In: Corner Code 84

1. Public Land Survey	T	4 S.	R	12 W.	<u>84</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. N/A, Recorded Plat N/A

5. Private Claims _____

James Young
CLERK-REGISTER

LIBER **1 1418**

Register of Deeds Stamp & File Number

I, GREGORY N. JENSEN, in a field survey on 07/17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4			8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B4 CENTER 1/4 POST SEC. 7, T.4 S., R.12 W.
- 1. HODGEMAN INTERSECTION OF 1/4 LINES, SET STAKE AND MEASURED WHITE OAK 12", S 37 1/2' W 47 LKS. (31.02'), WHITE OAK 20", N 36 1/2' W, 54 3/4 LKS. (36.13')
- 2. ED STRONG COUNTY SURVEYOR; FOUND STAKE CORRECT FROM WHITE OAK N 36 1/2' W, 54 1/2 LKS. (35.97') IRON PROMISED. (WELL SCREEN)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B4 CENTER 1/4 POST SEC. 7, T.4 S., R.12 W.
FOUND WELL SCREEN AT BISECTION OF NORTH AND SOUTH 1/4 LINE. (ON LINE AND 2645.68' TO N. 1/4 POST & 2644.35' TO S. 1/4 POST OF SECTION 7)

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-16-95
R.H.F.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B4 CENTER 1/4 POST SEC. 7, T.4 S., R.12 W. RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PROGRAM PEER GROUP ON NOVEMBER 16 1995. FOUND WELL SCREEN CALLED FOR BY ED STRONG COUNTY SURVEYOR AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REMOVED WELL SCREEN AND PLACED HARRISON MONUMENT.

- WEST FACE OF SQUARE CONC. FENCE POST EAST 1.7'
- 36" OAK, N. 85° E - 13.65'
- 6" HICK., N. 85° W - 30.10'
- 16" HICK., N. 45° W - 26.70'

Signed by *Gregory N. Jensen*
Surveyor's Michigan License No. 31593

