

APR 01 1996
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'95 DEC 18 PM 2 28

James D. Young
CLERK-REGISTERED

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4 S.</u> R <u>12 W.</u>	85
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. N/A, Recorded Plat N/A
5. Private Claims _____

LIBER 1 1413

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	•											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GREGORY N. JENSEN, in a field survey on 07/17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B5 SOUTH 1/4 POST SEC. 7, T.4 S., R.12 W.

- GLO SURVEY - SUGAR 12", S 25' W. 18 LKS (11.88'). A. 9", N 41' W. 10 LKS (6.6').
- HODGEMAN - SET STAKE AT PROPORTIONATE DISTANCE FROM 4-3. MARKED SUGAR 18", S 43' W. 192 3/4 LKS (67.82'). DOUBLE SUGAR 12", N 83 1/2' W. 199 LKS (131.34').
- WILKINS AND WEATON 8" BLACK WALNUT, N 45' E. 20.0'. 12" BLACK WALNUT, S. 77.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B5 SOUTH 1/4 POST SEC. 7, T.4 S., R.12 W.

- FOUND 4' LONG 1 1/2" DIA. PIPE 14' SOUTH OF TRAVELED CENTER LINE IN NORTH SHOULDER.
- FOUND PIT OF 8" WALNUT, N 45' E. 20'.
- FOUND STUMP OF 12", WALNUT SOUTH, 77.4' AS CALLED BY WILKINS AND WEATON.


RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93

R. G. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B5 SOUTH 1/4 POST SEC. 7, T.4 S., R.12 W. RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PROGRAM PEER GROUP ON NOVEMBER 16 1995. PLACED HARRISON IN MONUMENT BOX IN PLACE OF PIPE AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

- E. END CONC. CULVERT SOUTH - 33.0'
- 10" WALNUT N 45' E. - 13.90'
- 10" WALNUT N 45' W. - 25.70'
- TOP POINT BOULDER ON W. SIDE DRIVE TO HOUSE # 10481 S 45' E. 72.2'



Signed by Gregory N. Jensen Date 12/10/95
Surveyor's Michigan License No. 12/10/95 - 31593