

SURVEY & REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

DEC 14 PM 2 38

For corners in **COMMISSION**

Kalamazoo

(County)

Located In:

Corner Code #

Prairie Ronde Township

1. Public Land Survey

T 4 W R 12 S

B-7

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. Jans

CLERK-REGISTER

LEER 1 PG 1200

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 19, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829: U.S. Government Survey; Set 1/4 Section Post.

Beech 6" South 62 1/2° East 16 Lks
Ironwood 6" North 20° East 12 Lks

1872: S. Hodgman, County Surveyor; Large stone with drill hole.

Stone South 42 1/2° West 68 Lks

1894: E. Strong, County Surveyor; Found stone.

Elm South 30°± East 131 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found iron rerod (1/2" x 12"), 1 foot below surface, Down 40" below surface found stone with drill hole. This point is just off the North edge of pavement of "W" Avenue.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	19	20	21	22	23	24							
8													
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-15-94
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 South 1/4 Post Section 18, T. 4 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found drilled stone as called for in survey done by S. Hodgman in 1872 and is accepted as a careful and faithful perpetuation of the original corner's position. Placed iron in drill mark, placed 20" Harrison monument over iron and monument box over.

CL "W" Avenue South 11.0'
PK Nail in East Side 14" Cherry North 04° East 34.73'
PK Nail in West Side 10" Ash North 28° East 23.40'
PK Nail in East Side 10" Ash South 20° West 72.98'
PK Nail in North Side Power Pole South 62° West 100.33'

Signed by

Robert E. Snell

Date

12-12-94

Surveyor's Michigan License No.

9734