

**SURVEY &
REMONUMENTATION**

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 DEC 6 PM 3 56

COMMISSION

For corners in

Kalamazoo

(County)

Prairie Ronde Township

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>4</u> S R <u>12</u> W | <u>C-7</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

James J. [Signature]

CLERK-REGISTER

LIBER 1 PG 1189

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on May 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - U.S. Government Survey-Set Post to corner of Sections 17, 18, 19 and 20

Sycamore	24"	North	58½°	East	28 Lks
Lynn	8"	North	80°	West	8 Lks

1872 - S. Hodgeman, County Surveyor-Iron sleigh shoe from roots of Sycamore Witness.

1894 - Ed Strong, County Surveyor-Southeast Corner Section 18, found iron. Set stones around

Tamarac	6"	South	20½°	East	1.73½ Chains
Maple	4"	South	76 3/4°	East	1.36½ Chains

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - At surface found 1" x 6" iron pipe. At 3.5' below surface, found ½" x 18" rerod. At 4.3' below surface, found ½" x 18" twist iron. Found second twist iron at a depth of 5½'. At a depth of 7'± found iron sleigh shoe with stones around.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
6/21/94 *R. E. Snell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Southwest Corner Section 17, T. 4 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on June 21, 1994. Found iron sleigh shoe with stones around as called for in survey by Ed Strong dated 1872 and 1894 as well as other accessories as stated in "B" above and is accepted as a careful and faithful perpetuation of the original corner's position. Placed a 20" Harrison monument and monument box at surface of road.

PK Nail in Top of Guard Rail Post	South 50° West 39.40'	CL "W" Avenue
PK Nail in Southwesterly Side P/P (4' high)	North 35° West 44.95'	South 0.75'
PK Nail in Southerly Side Tamarac	North 60° East 93.48'	
PK Nail in End Post of Guard Rail	South 24° East 54.80'	CL "2nd" Street East 14'

Signed by *Robert E. Snell* Date 12/3/94
Surveyor's Michigan License No. 9734