

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

For corners in

Kalamazoo
(County)

KALAMAZOO COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 NOV 11 AM 8 54

James E. Spang
CLERK-REGISTER

- | | | |
|---------------------------------------|-------------------|---------------|
| 1. Public Land Survey | T 4S R 12W | D-3 |
| | T ___ R ___ | S 1/4 Cor. |
| | T ___ R ___ | Sec. 5 |
| | T ___ R ___ | Prairie Ronde |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | Township |
| | S ___ T ___ R ___ | |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | |
| | S ___ T ___ R ___ | |

LIBER

1 PG 1024

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3			●										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Thomas W.

I, Chettleburgh, in a field survey on October 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Strong 1901, Found stone and brick
Kalamazoo County Witnesses, two bricks 3' below iron
W. Smith 1977, Found 5/8" iron, set Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 5/8" iron in Monument Box
Found 2 bricks on end 3.0' below iron
Set 4" X 20" Harrison Monument over bricks
Centerline E-W road, "U" Avenue, South 3.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" X 20" Harrison Monument in Monument Box

Spike	NW	side	9" Maple	N39°E	262.63'
Spike	N	side	Power Pole	S70°E	132.88'
Spike	W	side	Power Pole	S4°W	99.09'
Spike	N	side	Power Pole	S80°W	154.76'

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**



Signed by Thomas W. Chettleburgh Date November 8, 1993

Surveyor's Michigan License No. 16036