

SURVEY &
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 08 2000

For corners in Prairie Ronde Twp.

SECTION

Kalamazoo Located in: Corner Code #
(County)

1. Public Land Survey T 4 S R 12 W D-05
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on June 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5				●									
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors, E. Lythe; set 1/4 Section post.

Elm 12" N. 05° W. 17 lks.
Ash 6" S. 28 1/2° E. 131 lks.

1872: S. Hodgman, Deputy County Surveyor; stone, said to be in place of original stake. Did not verify it as no traces of witnesses were to be found.

1893: E. Strong, County Surveyor; found good. Set brick.

Cherry 16" S. 3° ± W. 61 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1973: J. Corbit, R.L.S. #3101; LCRC L-1, P-437, 1/2" iron/brick/stone.

Fence Corner South 25.85'
Power Pole N. 30° E. 33.29'

1999: Found a railroad spike in pavement near surface. Found iron below railroad spike. 2 brick on end around iron and iron was over 6" x 6" x 6" stone with drill mark with several slightly smaller stones around. Crockery was found over 6" x 6" x 6" stone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 9-9-1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-05: South 1/4 post, Section 8, T. 4 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 9, 1999 and is accepted as the best available evidence of the position of the original corner. Found 6" x 6" x 6" stone with crockery, brick, iron and railroad spike over. Stone set by Samuel Hodgman, Deputy County Surveyor in 1872 survey with brick set by E. Strong, County Surveyor in 1893 survey. Placed 20" Harrison monument in monument box over stone.

PK Nail in South Side	Power Pole (new)	N. 32° E.	34.34'
PK Nail in North Side	36" Maple	S. 70° E.	75.61'
Southwest Corner	Railroad Rail Fence Corner	S. 03° E.	26.53'
Center	Irrigation Pump	N. 12° W.	78.63'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-15-1999