

SURVEY & REMONUMENTATION

FEB 26 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER PAGE 268

For corners in

SECTION

| | | |
|------------------------------------|-------------------------|--------------|
| <u>Kalamazoo</u> | Located In: | Corner Code# |
| (County) | | |
| Prairie Ronde Township | | |
| 1. Public Land Survey | T 4S R 12W | E-4 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ T _____ R _____ | _____ |
| Property in Sec. | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '97 DEC 23 PM 12 56
 Clerk - Register

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary D. Hahn, in a field survey on June 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | ● | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1829 - Quarter post established by U.S. Deputy Surveyor E. H. Lytle.
 Witnesses: Lynn 10 N 60 deg. E 10 L
 Beach 12 S 57 deg. W 23 L

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 11/20/97 *R. G. H.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found 1/2 inch capped iron (RLS 9734) in centerline of gravel road. Removed iron and dug 16 inches to find a 6" x 8" pointed stone directly beneath the 1/2 inch capped iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4, East Quarter Post Section 8, Town 4 South, Range 12 West, ratified by Kalamazoo County Remonumentation Peer Group on November 20, 1997. Position of stone is accepted as the best available evidence of the position of the original corner. Set a 12" Harrison Monument in a monument box directly over stone. Buried mon. box under gravel.

Witness Ties: Found PK nail in 12" Hickory East 78. 25 feet.
 Found PK nail in power pole S 20 deg. E 146.26 feet.
 Set 1/2 inch rebar in ditch N 45 deg. W 23.58 feet.
 Set 1/2 inch rebar in ditch West 14. 56 feet.



Signed by *Gary D. Hahn*
 Surveyor's Michigan License No. 38116

Date 12/19/97