

**SURVEY & REMONUMENTATION**

1  
2  
FEB 26 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 265

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code#
(County)		
Prairie Ronde Township		
1. Public Land Survey	T 4S R 12W	E-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
'97 DEC 23 PM 12 56  
Clerk - Register  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary D. Hahn, in a field survey on August 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - Southwest corner established by U.S. Deputy Surveyor E. H. Lytle.  
Witness Ties: Ash 10 S 10 1/4 deg. E 22 lks.  
White wood 24 S 79 deg. W 47 lks.  
Date ? - KCRC witness tie notes: RR spike/stone  
Power pole S 76.00 feet  
26" Beach N 45 deg. E 49.16 feet  
32" Twin Walnut N 45 deg. W 45.74 feet

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
11/20/97 R.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found PK nail in asphalt. Found bolt 0.5 feet deep directly below PK nail. Found upside down RR spike with notch directly below PK nail 1 foot below road surface. Found 6" x 6" stone with an X chiseled in it 1.5 feet below road surface with broken brick around. Stone is 0.13 feet north and 0.05 feet east of PK nail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5, Southwest Corner Section 9, Town 4 South, Range 12 West, ratified by Kalamazoo County Remonumentation Peer Group on November 20, 1997. Position of 6" x 6" stone is accepted as the best available evidence of the position of the original corner. Set a 12" Harrison Monument in a monument box directly over stone.

Witness Ties: Found PK nail in east face of power pole South 76.41 feet.  
Found PK nail in west face of a 32 inch Beach north 45 deg. E 49.16 feet.  
Found PK nail in 35" Twin Walnut N 45 deg. W 45.69 feet.  
Set 1/2 inch rebar S 45 deg. W 37.29 feet (under a bush).



Signed by [Signature]  
Surveyor's Michigan License No. 38116

Date 12/19/97