



LC-000081  
Page: 1 of 1  
12/17/1999 02:03P  
Bk-2 Pg-534

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Prairie Ronde Twp.

|                                       |                            |               |
|---------------------------------------|----------------------------|---------------|
| <u>Kalamazoo</u><br>(County)          | Located in:                | Corner Code # |
| 1. Public Land Survey                 | T <u>4</u> S R <u>12</u> W | <u>H-07</u>   |
|                                       | T _____ R _____            | _____         |
|                                       | T _____ R _____            | _____         |
|                                       | T _____ R _____            | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____    | _____         |
|                                       | S _____ T _____ R _____    | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____    | _____         |
|                                       | S _____ T _____ R _____    | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                            |               |
| 5. Private Claims                     |                            |               |

SURVEY &  
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: United States Government Surveyors; E. Lythe; set 1/4 post (In swamp).  
Tam 12" S. 8 3/4° E. 182 lks.
- 1873: E. Strong, County Surveyor; stone, from 1 U.S. dead.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1989: Ingersoll, Watson & McMachen, Al McMachen, RLS #16935; found pipe - no witness.
- 1999: Found 1" x 8" pipe 8" below surface. Dug 7' deep hole and probed another 4-5'. Deep fill in road. Measured East to Southeast corner 2,652.59' and West to Southwest corner 2,658.29'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-07: South 1/4 post, Section 15, T. 4 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 9, 1999 and is accepted as the best available evidence of the position of the original corner. Found 1" x 8" pipe. Placed 20" Harrison monument in monument box.
- |                      |            |           |        |
|----------------------|------------|-----------|--------|
| PK Nail in West Side | 12" Elm    | S. 32° E. | 54.95' |
| PK Nail in West Side | 26" Poplar | S. 10° E. | 43.62' |
| PK Nail in West Side | 22" Poplar | S. 40° W. | 56.91' |
| PK Nail in East Side | 12" Poplar | North     | 36.78' |

Signed by Robert E. Snell Date 12/16/99  
Surveyor's Michigan License No. 9734

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
9/9/99 R.E.S.