

1  
2

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in PRAIRIE RONDE TWP  
KALAMAZOO  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>4S.</u>	R	<u>12W.</u>	I-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		R		
	S		R		
3. Miscellaneous	S		R		
Property in Section	S		R		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

6. IWM Job No. 30465

I, Allen H. McMachen, in a field survey on August 28, 1997  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - E.H. Lytle, D.S., Intersected North boundary 55 lks West of post at intersection, corner of Sections 2 & 3, R. Oak 14" S. 75° E. 40 lks., W. Oak 18" S. 74° W. 72 lks..

1873 - Ed Strong, C.S., "Has nothing set and no U.S.....".

1874 - F. Hodgman, Surveyor (for Survey in Section 3), "Prolonged line 3 (SE cor.) - 6 (E 1/4 cor.) and found stake. Set stake & stone & marked Y. Oak 10" S. 54 3/4° E. 86 lks., Texas corner stone is 1.24 ch. (81.84') East."

1902 - Ed Strong, C.S., "Found both corners, U.S. stump still in road."

1973 - Ingersoll, Watson & McMachen, "Set iron rod 81.84' West of SE cor., Sec. 34, Texas Twp. (stone) & on line between said SE cor & SW cor., Sec 34, Texas Twp., Fence post West 24.00', N. & T. in 4" Elm S. 45° W. 15.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod 81.87' West of SE cor., Sec 34, Texas Twp. (standard marker), Removed iron and dug to 3' below grade & found no additional evidence of corner. Replaced iron.

SURVEY &  
REMONUMENTATION  
NOV 25 1998  
SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Found iron rod is accepted as a careful and faithful reestablishment of the position of the original corner. Replaced found iron rod with a 30" Harrison Monument, Accessories:

Iron rod N. 40° W. 20.12'  
Nail in 16" Cherry S. 15° W. 33.95'  
Nail in 8" Triple Oak N. 80° E. 81.99'  
Harrison Monument (SE cor., Sec. 34, Texas Twp.) East 81.87'

LIBER 2 PAGE 328  
STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1998 OCT 12 PM 1 29  
J. J. [Signature]  
CLERK - REGISTER  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	J	K	L	M
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12/18/97 R.E.S.



signed by Allen H McMachen  
Surveyor's Michigan License No. 16935

Date 10/9/98