

FEB 08 1999

LIBER 2PAGE 391

SECTION

LAND CORNER RECORDATION CERTIFICATE

PRAIRIE RONDE TWP Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KALAMAZOO (County)

Located In:

Corner Code #

1. Public Land Survey	T	4S.	R	12W.	I-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '98 DEC 15 PM 3 50
 Clerk - Register
[Signature]

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 30465-97

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on September 25, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - E.H. Lytle, D.S., Set quarter Section post, Wh. Oak 18" N. 59 $\frac{1}{4}$ ° E. 18 lks., Wh. Oak 18" S. 11° W. 46 lks.
- 1874 - F. Hodgman, Surveyor, "Found stone." (N.W. cor., W. $\frac{1}{4}$ cor., and S.W. cor. of Sec. 2 were on a straight line.)
- 1879 - F. Hodgman, C.S., "Stone of former survey correct."
- 1902 - Ed Strong, C.S., "Found stone, Hickory 8" S. 25° W. 127 lks., 1 U.S. stump in road.
- 1902 - Ed Strong, C.S., Found stone, hickory good, U.S. stump (measured from W $\frac{1}{4}$ corner North 2810.94 feet to N.W. corner).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box, removed iron and box, dug and found very old iron drill shaft rusted into two pieces about 12" long, 0.2' West and 0.2' South of surface iron. Removed drill shaft and continued digging to a depth of 5 feet and found no further evidence of corner. Area around corner appears to have been cut $\pm 2'$ - $3'$. Measured North 2808.35 feet to standard marker at N.W. corner and measured South 2660.72 feet to ratified position of S.W. corner.

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 12-18-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found drill shaft is accepted as the best available evidence of the position of the original corner. Replaced drill shaft with a 30" Harrison Monument with mon. box over, Accessories:

- Iron rod with IWM cap N. 40° W. 47.11'
- Nail & Tab in NW side 24" Oak N. 40° E. 37.00'
- Nail & Tab in South side 14" Oak N. 70° E. 33.85'
- Nail & Tab in NE side of U. Pole S. 40° E. 38.34'
- In centerline of 8th Street and 2' South of centerline "TU" Avenue



Signed by *Allen H. McMachen* Date 12/15/98
 Surveyor's Michigan License No. 16935