



LC-000057
Page: 1 of 1
10/29/1999 03:52P
Bk-2 Pg-510

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Prairie Ronde Twp.

**SURVEY &
REMONUMENTATION**

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

Kalamazoo Located in: Corner Code #
(County)

1. Public Land Survey T 4 S R 12 W I-07
T R
T R
T R

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Snell, in a field survey on May 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors, E. Lythe; corner to Sections 14, 15, 22 and 23, on an Ash 24".
- 1873: E. Strong, County Surveyor; Black Walnut 12° S. 12° E., 45 1/2 lks. Set from oral evidence and signs of hole.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Found 18" long bolt in monument box over 16" x 8" dia. Stone with "x" on top 2.5' below the surface of the road. Bolt was 0.27' North of "x" on stone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-9-1999 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-07: Southwest corner, Section 14, T. 4 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 9, 1999 and is accepted as the best available evidence of the position of the original corner. Found 18" long bolt in Monument box over stone with "x" believed set by E. Strong, County Surveyor in 1873 survey. Placed 20" Harrison monument in monument box over stone with "x".

Double Head Nail/Large Tab in West Side	Power Pole	N. 50° E.	48.15'
1/2" Iron with	Red Cap	S. 44° E.	32.15'
1/2" Iron with	Red Cap	S. 60° W.	35.03'
1/2" Iron with	Red Cap	N. 40° W.	43.02'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 10/25/99