

SEP 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Prairie Ronde Township, Kalamazoo (County)

Located In:

Corner Code #

- 1. Public Land Survey T 4S. R 12W. J-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

CLERK - REGISTER

Handwritten signature

SEP 26 PM 3 27

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD

LIBER 2 PAGE 297 Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell J-2 is shaded.

I, Allen H. McMachen, in a field survey on September 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.

1879 - F. Hodgman, C.S., "Set stake by measure from South quarter corner, Section 35, T. 3 S., R. 12 W.."

1902 - E. Strong, C.S., Map shows jog at North quarter corner at 75 1/2 (49.83') & measure to Center quarter corner at 40.93 ch. (2701.38').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner marker found. Location of North quarter corner reestablished by measuring West 49.83' from the South quarter corner, Section 35, Texas Township (standard marker) and placed on the South line of the Southwest quarter, Section 35, Texas Township. Jog was developed from Hodgman jog of 1.24 ch. (81.84') at Northwest corner, Section 2 and government jog of 27 links (17.82') at Northeast corner, Section 2. Measured South 2699.63 feet to historic location of Center quarter corner (previously found stone).

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 12-18-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Location of North quarter corner as described in Section "B" above is accepted as the best available evidence of the position of the corner. Placed 30" Harrison Monument (15" deep) at said location, Accessories:

- Nail & Tab in South side 22" Triple Oak N. 50° E. 66.19'
Nail & Tab in South side 10" Oak N. 70° E. 52.98'
Nail & Tab in North side 20" Oak East 51.05'
Standard marker at South quarter corner, Section 35, Texas Township East 49.83'



Signed by [Signature] Surveyor's Michigan License No. 16935

Date 2/24/98