

SURVEY & REMONUMENTATION

1
2
SEP 14 1998

SECTION LAND CORNER RECORDATION CERTIFICATE

For corners in Prairie Ronde Township
Kalamazoo (County)

Filing Requirement of Act 74, Mich. P.A. 1970
Located In: _____ Corner Code # _____

- | | | | | | |
|--------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>4S.</u> | R | <u>12W.</u> | <u>J-2</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 2 PAGE 296
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 MAR 26 PM 3 37
CLERK - REGISTER
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 23, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.

1879 - F. Hodgman, C.S., "At intersection of quarter lines set stake, Bl. Walnut 12" S. 41 $\frac{3}{4}$ " W. 54 lks, Mulberry 3" N. 9 5/6" W. 46 lks.. Also set stakes on the North and South quarter line at 12.50 ch. and 20.00 ch. North from the center of the Section.

1980 - Wilkins & Wheaton (survey of Southwest quarter, Section 2), "Found large stone-only stone." Found iron in concrete 16.75' North of small white spot on top of stone. Meas. West 2672.54' to West quarter corner. Meas. South 2662.04 feet to South quarter corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Stone at 1980 location was not recovered. Placed Center quarter corner at 1980 location, by measuring East 2672.54' from West quarter corner and by measuring North 2662.04' from South quarter corner. Said location is 2.44 feet East and 1.57 feet South of intersection of quarter lines.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-19-1998**

R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Location of stone found in 1980 is accepted as the best available evidence of the position of the corner. Placed 30" Harrison Monument at said position, Accessories:

- Iron in concrete North 16.74'
- Nail & Tab in South side of 28" Oak West 30.31'
- Nail & Tab in West side 8" Elm S. 35° W. 23.36'
- Nail & Tab in West side 10" Walnut S. 25° W. 44.90'
- ±12' West of West edge tilled field



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 2/24/98