

OCT 06 1997

COMMISSION

LIBER 2 PAGE 213

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

7.
2
For corners in Prairie Ronde Township
Kalamazoo (County)

Located In: Corner Code #

- 1. Public Land Survey T 4S. R 12W. K-11
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Section S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 SEP 26 AM 11 10
 Clerk - REGISTER
J. J. Johnson

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 10, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - E. H. Lytle, D.S., Set post corner, Secs 25, 26, 35 & 36, Beech 24" East 33 lks., R. Oak 30" S. 37° W. 53 lks.
- 1869 - F. Hodgman, C.S., "Found old stake, standing witnesses gone. Drove a Bl. Walnut stake & marked Maple 12" N. 76° E. 17 lks." Duncon promised to put down a stone & blacksmith cinders.
- 1870 - F. Hodgman, C.S., "Southeast corner [Sec. 26] planted by former survey".
- 1872 - S. Hodgman, D.C.S., Drove Oak stake witness good.
- 1882 - F. Hodgman, C.S., "Set stone in place of stake, bearing trees standing".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone with "X" at NW cor. of Lot 84, plat of "Woodbrook No. 3" L. 38, Pg. 14.

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 9-18-1997.
R. J. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone is accepted as a careful and faithful perpetuation of the position of the original corner. Removed found stone and replaced with Harrison monument, Accessories:

- Nail & Tab in East side of 16" Elm N. 05° E. 16.39'
- Nail & Tab in North side of 15" Cherry West 13.36'
- N.W. cor. of house #16016 S. 70° E. 95.30'
- S.W. cor. of house #16016 S. 50° E. 164.54'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

9/25/97