

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 4 DEC 14 PM 2 38

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

Prairie Ronde Township

- | | | |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey | T <u>4</u> S R <u>12</u> W | M-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James [Signature]

CLERK-REGISTER

LIBER 1 PG 1201

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: U.S. Government Survey; Set Post Corner to Sections 12 and 13 in prairie and raised mound.

1889: F. Hodgman, County Surveyor; Found stone and bearing trees of resurvey all in place. Set Post (3" Tile) (Done for Southwest Corner Section 7, T. 4 S., R. 11 W.)

NOTE: Prairie Ronde M-5 is Common Corner Schoolcraft A-5.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 3/8" rod below pavement and top section of 3" tile broken and laying on it's side, below rod. Found second section of tile (2' in length) upright.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-21-94**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Southeast Corner Section 12, T. 4 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found 3" round tile (2' Section) as called for in 1889 remonumentation survey by F.Hodgman; and is accepted as a careful and faithful perpetuation of the original corner's position. Placed 16" of 20" Harrison monument with monument box over.

- PK Nail in East Side 34" Maple North 33° West 89.55'
- PK Nail in East Side 30" Maple North 20° West 141.54'
- PK Nail in West Side Power Pole North 15° East 156.44'
- PK Nail in West Side Power Pole South 12° East 102.18'
- CL 12th Street West 1.5'

NOTE: This corner is in common with A-5 Southwest Corner Section 7, T4S,R11W

Signed by Robert E. Snell Date 12/14/94

Surveyor's Michigan License No. 9734