



LC-000082

Page: 1 of 1
12/17/1999 02:03P
Bk-2 Pg-535

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Prairie Ronde Twp.

Kalamazoo
(County)

Located in: _____ Corner Code # M-08

1. Public Land Survey T 4 S R 12 W
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

SURVEY &
REMONUMENTATION
FEB 08 2000
SECTION
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Snell, in a field survey on Nov. 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors, J. Mullett; set 1/4 Section post. No bearing trees near and too wet to raise mound.
Note: 38.00 chains (2,508.00') left prairie and entered marsh (132' into marsh).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1935: Wilkins & Wheaton Engr. Co.; placed iron on bisection 38.61' South of corner established for W. 1/4 (A-08) Section 19, Schoolcraft.
1999: Found 3/4" x 22" iron laying on its side in swamp about 38.61' South of iron found as West 1/4 post Section 19, Schoolcraft. Placed 30" Harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-08: East 1/4 post, Section 24, T. 4 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 9, 1999 and is accepted as a careful and faithful re-establishment of the position of the original corner. Found 3/4" x 22" iron laying on its side. Found 3/4" x 22" iron 38.61' North of corner as established in 1935 survey as West 1/4 (A-08) Section 19, Schoolcraft (now Harrison Monument). Placed 30" Harrison marker in its place in swamp.

Iron (Found)	In North right-of-way GTW Railroad	S. 0°-12' W.	176.40'
Pk Nail in East Side	14" Wild Cherry	S. 5°-22' W.	129.64'
Pk Nail in South Side	12" Willow (center trunk)	N. 82°-36' W.	310.07'
Center	Harrison Monument (A-08 Schoolcraft)	North	38.61'

Signed by Robert E. Snell
Surveyor's Michigan License No. _____

Date 12/16/99

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/9/99