



LC-000084
Page: 1 of 1
12/17/1999 02:03P
BK-2 Pg-337

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Prairie Ronde Twp.

Kalamazoo Located in: _____ Corner Code # _____
(County)

This corner common to
SW corner Sec. 19, Schoolcraft

1. Public Land Survey	T <u>4</u> S. R. <u>12</u> W	<u>M-09</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on Oct. 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors, R. Clark; entered West boundary at post. Mound in prairie.
- 1889: F. Hodgman, County Surveyor; "Found old stake at intersection of fences on West side of fence post for board fence running East. Set post."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1935: Wilkins & Wheaton Engr. Co.; found tile in fence.
- 1962: R. Sayers, R.L.S. #4727; said to have had Northwest corner of Section 30 (Southwest, Section 19, T. 4 S., R. 11 W.). No description of corner.
- 1999: Found tile 15" below surface - 3" round with "x" on top 24" in length 24" below surface. Top 12" of tile lost. All fences gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-09: Southwest corner, Section 24, T. 4 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on November 18, 1999 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile 24" in length with "x" on top as set by F. Hodgman in 1889 Remonumentation survey. Removed tile and placed 30" Harrison monument 24" deep with 4, 1/2" x 18" irons at cardinal compass points 1" above top of monument. No witnesses near.

Center	3/4" iron (Harrison Monument)	Assumed South	2,657.53'
Center	Harrison Monument (C-09), T4S,R11W)	S. 88°-14'-59" E.	5,124.51'
Center	Harrison Monument (M-08), T4S,R12W)	N.08°-08'-52" E.	2,657.43'

Signed by Robert E. Snell Date 12/17/99
Surveyor's Michigan License No. 9734

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11/18/99 R.E.S.