

FEB 08 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Prairie Ronde Twp.

Kalamazoo Located in: Corner Code #

(County)
This corner common with A-10
Section 31, Schoolcraft

Barcode with text: LAND CORNERS, LANDCOR-Kalamazoo, LC-000103, Page: 1 of 1, 12/30/1999 01:18P, Bk-2 Pg-556

- 1. Public Land Survey T 4 S R 12 W M-10
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Robert E. Snell, in a field survey on Nov. 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (10, M) contains a star symbol.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors, J. Mullett; raised mound in prairie, set post.
1826: United States Government Surveyors, R. Clark; entered West boundary at post (both Northwest and Southwest corners, Section 30, T. 4 S., R. 11 W., Schoolcraft Twp.).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1966: Kalamazoo County Road Commission; iron rod at station 24+32.2 from center 1/4 post, Section 30, Schoolcraft, delta angle = 0°-47' left, fence line North 28.0', fence line South 29.1±, West 1/4 post Section, Section 30, Schoolcraft.
1999: Dug hole in shoulder of road at bisection of East line of Section 25, Prairie Ronde (also Section 30, Schoolcraft Township, T. 4 S., R. 11 W.). Found no evidence of previous corner. Placed 3/4" x 22" iron on bisection of tiles at Northwest corner and Southwest corner Section 30, Schoolcraft (common with Northeast and Southeast corners, Section 25, Prairie Ronde, T. 4 S., R. 12 W.). Tiles ratified November 18, 1999. Found iron in monument box near center line of "XY" Avenue - 10± West and 12' South of true bisection.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10: East 1/4 post, Section 25, T. 4 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 9, 1999 and is accepted as a careful and faithful re-establishment of the position of the original corner. Placed 30" Harrison monument in monument box on bisection of East line of Section 25, Prairie Ronde Township line.

Table with 4 columns: Monument/Accessory, Direction, Distance, and Ratified Date.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 12-09-1999

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12/23/99