

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0347

For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 11W	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTERED  
LAKE COUNTY, MI.  
SEP 12 3 07 PM '96  
REGISTER OF DEEDS  
Francis J. Deane

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on August 7, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-4 - 1/4 Corner common to Section 7 & 8, T17N, R11W, Chase Twp., Lake Co., Mi.

1838 - J. Hodgson, G.L.O.

- #1 - 9" Beech N17°E 28 Links
- #2 - 11" Elm S31°W 40 Links
- #3 - Stream South 0.5 Chains

Undated George Johnson (prior 1920)

- Plow Point
- #4 - 5" Elm S27°E 53 Links
- #5 - 5" Elm S30°W 116 Links

1980 - R.L. Wetherell, LS 24624

- Found Plow Point
- #6 - 18" Cherry S1°W 77.92'
- #7 - 20" Maple S56°W 94.88'
- #8 - 14" Elm N86°E 28.07'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 - 1/4 Corner common to Section 7 & 8, T17N, R11W, Chase Twp., Lake Co., Mi.

I found a plow point 35 feet North of creek and 6 feet East and 5 feet South of Fence Post.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN  
DATE 8-27-96 *RLW.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 - 1/4 Corner common to Section 7 & 8, T17N, R11W, Chase Twp., Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap over the plow point, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 7" x 6' Iron Pipe N40°W 8.6'
- 22" Cherry S2°W 77.90' (60d spike in W. side) #6
- 24" Maple S57°W 94.90' (60d spike in E. side) #7
- 20" Elm N86°E 28.00' (Found nail in S. side) #8

Signed by Robert L. Wetherell  
24624

Date August 28, 1996

Surveyor's Michigan License No. \_\_\_\_\_

