

RECORDED

NOV 15 1994

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0238

For corners in

| Lake (County) | Located In: | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 17N R 11W | D-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

REGISTERED
 LAKE COUNTY, MI.
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number
 Oct 7 3 47 PM '94
Registrar H. Deane

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Robert L. Wetherell, in a field survey on August 3, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 - South 1/4 corner Section 32, T17N, R11W, Lake County, Michigan.
- 1837 - John Hodgson, G.L.O.
#1 - 10" Pine N28°E 43 Links
#2 - 8" Maple N76°W 41 Links
- 1929 - E.E. Sours, Engineer
Developed plat of "Stanley Park".
Showed distance of 2633' more or less to Southeast corner of Section 32.
- 1979 - R.L. Wetherell, LS 24624
Found 1" Pipe
#3 - 10" W. Oak S45°W 156.60'
#4 - 24" Maple North 35.22'
#5 - 24" Maple N61°E 55.84'
L.C.R.C. #501.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 - South 1/4 corner Section 32, T17N, R11W, Lake County, Michigan.

I found 1" x 24" pipe 6 feet South of East and West road. I measured a distance to the Southeast corner of Section 32 of 2631.3 feet. Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 - South 1/4 corner Section 32, T17N, R11W, Lake County, Michigan.

I replaced 1" pipe with 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

26" Maple N56°E 55.87' (60d spike in N.W. side of tree) (#5)
24" Maple N1°W 35.22' (60d spike in E. side of tree) (#4)
14" W. Oak S43°W 156.50' (60d spike in N.W. side of tree) (#3)
6" R. Pine N40°W 59.14' (60d spike in S.W. side of tree)

Signed by Robert L. Wetherell Date October 4, 1994
Surveyor's Michigan License No. LS 24624

