

SUB. [REDACTED]
RECORDATION

NOV 15 1994

COMMISSION

LAND CORNER RECORDATION CASE NO. 0239
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in LAKE

(County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 11W	G-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED
LAKE COUNTY, MI.
OCT 27 3 23 PM '94
REGISTER OF DEEDS
Chas. H. Deane

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-1 - Sec. corner common to Sections 3 & 4, Chase Twp., Lake Co., Mi., on North Township Line.
 - 1838 - John Hodgson, G.L.O.
 - #1 - 8" Beech S26°E 20 Links
 - #2 - 8" Beech S35°W 29 Lins
 - #3 - Standard corner East 14 Links
 - Undated - George Johnson, County Surveyor
 - Large stone
 - #4 - 15" Elm - S30°W 50.5'
 - 1979 - Robert L. Wetherell, LS 24624
 - 1/2" Rebar (Found)
 - #5 - P. Pole S53°E 69.56'
 - #6 - 10" Cherry N20°W 79.05'
 - #7 - 1/2" Re-bar East 9.24'
 - #8 - Elm Stump Southwest 50.5' (#4)
 - 1988 - Robert L. Wetherell, LS 24624
 - P. Pole S50°E 69.7' (#5)
 - 1992 - Robert L. Wetherell, LS 24624
 - P. Pole S53°E 69.72' (#5)
 - #9 - 24" Maple S11°W 259.70'
 - #10 - P. Pole N57°W 134.82'
 - #11 - Cor. Fence Post N42°W 47.38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-1 - Sec. corner common to Sections 3 & 4, Chase Twp., Lake Co., Mi., on North Township Line.

I found 1/2" re-bar in intersection of roads North, South, East and West. Condition of the accessores are: #1 Gone, #2, Gone, #3 Found in good condition, #4 Gone, #5 Found in good condition, #6 Gone, #7 Found in good condition, #8 Gone, #9 Found in good condition, #10 New Pole, #11 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 - Sec. corner common to Sections 3 & 4, Chase Twp., Lake Co., Mi., on North Township Line.

I set a 3/4" x 24" re-bar with a Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

 - P. Pole S53°E 69.72' (60d spike in N.E. side) (#5)
 - 24" Maple S11°W 259.70' (60d spike in W. side of tree) (#9)
 - P. Pole N57°W 132.86' (60d spike in S. side)
 - Standard Corner East 9.24' (3/4" x 24" re-bar with Lake County Brass Cap) (#3)

Signed by *Robert L. Wetherell* Date 10-26-94
LS 24624

Surveyor's Michigan License No. _____
RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *W. L. W.*
DATE 10-25-94

