

SURVEY & RECONSTRUCTION

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 024 I

For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 11W	I-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
*Robert L. Wetherell*

OCT 21 3 23 PM '94

RECORDED  
LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1 - Section corner common to Sections 2 & 3, on Township line, Chase Twp., Lake Co., Mi.

- #1 - 7" Beech S73°E 21 Links
- #2 - 8" Beech S43°W 21 Links
- Section corner 34 and 35, (T18N, R11W) East 23 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 - Section corner common to Sections 2 & 3, on Township line, Chase Twp., Lake Co., Mi.

I set this corner the G.L.O. record distance of 23 Links (15.18 feet) West of the found standard corner on the Township line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 - Section corner common to Sections 2 & 3, on Township line, Chase Twp., Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap in monument box, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 22" Maple N75°W 116.60'
- 10"-12" Twin Maple N68°E 116.60' (60d spike in S.E. side)
- Power Pole S61°E 111.89' (60d spike in N. side)
- Power Pole S51°W 74.53' (60d spike in S.E. side)
- Brass Cap Monument - East 15.18' (3/4" x 24" re-bar with Lake County Brass Cap)

Signed by Robert L. Wetherell Date 10-26-94

Surveyor's Michigan License No. 24624 RATIFIED BY THE LAKE CO. PEER REVIEW GROUP IN ACCORDANCE WITH P.A. 345

CHAIRMAN [Signature]  
DATE 10-25-94

