

DEC 9 1993

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0165

For corners in
Lake

(County)	Located in:		Corner Code #
	17N	11W	
1. Public Land Survey	T	R	L-5
	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

REGISTER OF DEEDS
Shirley M. DeLeon
 OCT 29 4 39 PM '98
 RECORDED
 LAKE COUNTY, MI.
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Robert L. Wetherell May 20, 98

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-5 - 1/4 Corner common to Sections 12 & 13, T17N, R11W, Lake Co., Mi.

- | | | |
|------------------------------|--|--|
| 1838 - J. Hodgson, G.L.O. | 1987 - Duane Wood, LS 24625 | 1992 - R.L. Wetherell, LS 24624 |
| #1 - 8" Beech S28°W 26 Links | L.C.R.C. - Liber 03, Pg. 51. | L.C.R.C. - Liber 003, Pg. 168. |
| #2 - 6" Beech N58°E 14 Links | Set 1/2" Iron in line with fence to South and in centerline of East-West road. | 1/2" Capped Iron |
| | #3 - N.E. Cor. Conc. Slab S30°W 34.2' | #6 - 5" Elm N58°E 51.40' |
| | #4 - 4" Birch S15°E 31.01' | #7 - 5" Elm N70°W 74.85' |
| | #5 - 6" Elm N30°E 38.2' | #8 - N.E. Cor. Tel. Riser S30°W 36.22' |
| | | #9 - P. Pole S55°E 147.73' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *R.L.W.*
DATE 10-27-98

L-5 - 1/4 Corner common to Sections 12 & 13, T17N, R11W, Lake Co., Mi.

I did not find any monument at this location, presumed iron was destroyed by road construction. Reset Iron from recovered accessories.
Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 - Found dead, #6 Found in good condition, #7 Found dead, #8 Found in good condition, #9 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 - 1/4 Corner common to Sections 12 & 13, T17N, R11W, Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.
5" Tamarack S66°W 68.18' (60d spike in N.W. side)
4" Cedar S32°E 37.64' (60d spike in S.W. side)
6" Elm N58°E 51.40' (60d spike in S. side) #6
14" R. Pine N5°E 48.48' (60d spike in W. side)
Power Pole S55°E 147.73' (60d spike in S.W. side) #9

Signed by *Robert L. Wetherell*
Surveyor's Michigan License No. 24624

Date 10-29-98

