

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0251

For corners in
Lake

COMMISSION

REGISTER OF DEEDS

OCT 27 9 26 AM '94

RECORDED
LAKE COUNTY, MI.

(County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 11W	M-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Wetherell, in a field survey on August 12, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 - S.E. corner Section 36, T17N, R11W, Lake Co., Mi. (corner common to Townships 17-11, 16-11, 17-10 & 16-10)	1974 - Ed Benkert, L.S. 1237	1993 - R.L. Wetherell, LS 24624
1837 - John Hodgson, G.L.O.	Iron Bar	Iron Bar
#1 - 8" Sugar N55°E 42 Links	#3 - P. Pole N29°E 64.0'	#5 - P. Pole N34°E 63.90' (#3)
#2 - 18" Sugar S67°W 40 Links	#4 - Fence Post N45°W 46.0'	#6 - Conc. Fe. Post N38°W 46.8' (#4)
1879 - J.C. Brewster	Survey recorded in Liber 311, Page 420, Osceola Co.	#7 - 40" Cottonwood S23°W 91.00'
Old Stake Found and one witness. Rock and Elm Stake 4'x4'x34" Long. From Newaygo County Surveyors office. Book A, Page 27.		#8 - 30" Catalpa S62°E 84.52'
		Recorded Act 74 in Mecosta Co.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 - S.E. corner Section 36, T17N, R11W, Lake Co., Mi. (corner common to Townships 17-11, 16-11, 17-10 & 16-10)

I found the iron bar that I had used in 1993. Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 315
CHAIRMAN [Signature]
DATE 10-25-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 - S.E. corner Section 36, T17N, R11W, Lake Co., Mi. (corner common to Townships 17-11, 16-11, 17-10 & 16-10)

I replaced the iron bar with a 3/4" x 24" Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- P. Pole N34°E 63.90' (Found nail and tag marked 1237) (#3)
- Concrete Post N38°W 46.8' (#4 & #7)
- 40" Cottonwood S23°W 91.00' (60d spike in E. side of tree) (#7)
- 30" Catalpa S63°E 84.62' (60d spike in N. side of tree) (#8)

Signed by Robert L. Wetherell
24624

Date 10-26-94

Surveyor's Michigan License No. _____

