

**SURVEY &
REMONUMENTATION**

JAN 14 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

Lake _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 12W	C-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on November 3, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-8 - 1/4 Corner common to Sections 19 & 20, T17N, R12W, Lake Co., Mi.

- | | |
|------------------------------------|-------------------------------------|
| <u>1838 - John Hodgson, G.L.O.</u> | <u>1955 - George Blass, LS 5489</u> |
| #1 - 7" Cherry S22°W 16 Links | "Found 4" x 4" x 4' Square |
| #2 - 7" Cherry N57°W 9 Links | Cherry Stake". |
| Stream North 0.1 Chains | #3 - 12" B. Oak N38°W 32.84' |
| | #4 - 8" W. Pine S23°30'E 18.55' |
| | #5 - 8" Tw. B. Oak S84°E 73.81' |

- 1976 - Robert A. Griffin, 13584
L.C.R.C. - Liber 02, Pg. 271
"Found witnesses to corner by
G.H. Johnson."
Set 2" x 60" Pipe with brass cap
#6 - 4" x 7' Post East 32.65'
#5 - 14" Tw. Oak S84°E 74.04'
#4 - 12" W. Pine S23°E 18.55'
#7 - 5" B. Oak S51°W 44.84'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: #8 - 3" Maple N63°W 12.82'

C-8 - 1/4 Corner common to Sections 19 & 20, T17N, R12W, Lake Co., Mi.

I found a 2" pipe with brass cap 7 feet South of Creek.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found Stump, #4 Found Down, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.D.W.
DATE 12-10-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 - 1/4 Corner common to Sections 19 & 20, T17N, R12W, Lake Co., Mi.

I accepted the 2" pipe with brass cap as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 16" Tw. B. Oak S80°E 74.11' (5/8" Rod in S. side) #5
13" W. Pine N67°E 61.55' (60d spike in S.E. side)
7" Maple N60°W 12.85' (dock spike in S. side) #8
9" Maple S53°W 44.89' (dock spike in S. side) #7

Signed by Robert L. Wetherell

Date 12-12-97

Surveyor's Michigan License No. 24624

RECORDED
LAKE COUNTY MI.
LIBER 004 PAGE 0093

DEC 12 11 38 AM '97

Lucinda H. Dickson
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

