

FEB 18 1994

COMMISSION

LAKE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED LAKE COUNTY, MI.

LIBER 003 PAGE 0199

DEC 13 3 42 PM '93

Secordia H. Dechant REGISTER OF DEEDS

For corners in

Table with columns: Lake (County), Located In: (T, R, S, T, R, S, T, R), Corner Code -## (F-13)

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13

I, Robert L. Wetherell, in a field survey on December 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 - S.1/4 Corner, Section 33, T17N, R12W, on the County Line

1837 - John Hodgson, D.S., G.L.O. Placed wood post #1 7" Pine N10°E 13 Links #2 7" Pine N59°W 37 Links

1936 - W. Welton, USFS Technican Set Iron Rod #3 USFS Pine Post N03°E 0.3 Chains (19.80') (Reported Post being North of Road)

1899 - Delos Anderson Newaygo Co., Surveyor #4 14" W. Pine S32°W 36 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 - S.1/4 Corner, Section 33, T17N, R12W, on the County Line

I found the Pine Post by the USFS lying on the ground on the South side of the road, I was unable to recover its original location. I did not find the corner or any of the accessories stated in "A" above.

In 1899, Delos Anderson (Newaygo Co. Surveyor) reported a distance to the S. 1/4 corner of Section 4, T16N, R12W, 82.17 Chains (5423.22') and a distance from the S. 1/4 of Sec. 4, T16N, R12W to the Southwest corner of Section 4, T16N, R12W 43.02 Chains (2839.32'). I recovered the S. 1/4 corner and S.W. corner of Section 4, and measured a distance between them of 2837.4', consistent with Anderson's. I reset the 1/4 corner (Sec. 33, and Sec. 4) at a distance of 5423.2' North of the S. 1/4 corner (Sec. 4) and 33' West of an extension of a North and South right of way fence. This position falls 12.5' West more or less and 15.2' more or less North of a proportionate split between Section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 - S.1/4 Corner, Section 33, T17N, R12W, on the County Line

I set 3/4" x 24" re-rod with Lake County Brass Cap, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 17" W. Oak S83°W 41.49' (60d spike in South side of tree)
13" W. Oak N08°E 10.76' (60d spike in SE side of tree)
15" B. Oak N55°E 61.77' (60d spike in SE side of tree)
12" Tw. W. Oak S84°E 50.60' (60d spike in NE side of tree)

Signed by Robert L. Wetherell Date 12-13-93

Surveyor's Michigan License No. LS 24624

Approved by Peer Review Group December 6, 1993 Robert L. Wetherell, County Representative

