

FEB 18 1994

LAKE COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBR 003 PAGE 0201 DEC 13 3 42 PM '93

For corners in COMMISSION

Joseph H. Dechant REGISTER OF DEEDS

Table with columns: Lake (County), Located In: (T, R), Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, Robert L. Wetherell, in a field survey on Nov. 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 1/4 corner Section 34, T17N R12W, on County Line

1837 - John Hodgson, D.S., G.L.O. #1 16" W. Pine N70°W 26 Links #2 18" W. Pine N23°E 60 Links

1952 - George Blass, LS 5489

Set 1" iron pipe by single proportionate distance #3 14" W. Oak N40°W 71.20' #4 8" Maple N85°E 76.95' #5 10" Tw. W. Oak S25°W 72.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 1/4 corner Section 34, T17N R12W, on County Line

I found the 1" iron pipe by George Blass and accepted as the true location. Condition of recorded witnesses: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found stump, #5 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 1/4 corner Section 34, T17N R12W, on County Line

I set a 3/4" x 24" re-bar with Lake County Brass cap inside the existing 1" pipe, and is accepted as a careful and faithful re-establishment of the position of the original corner.

18" W. Oak N40°W 71.17' (OBT) (60d spike in the NE side of tree) #3 14" Tw. W. Oak S25°W 72.95' (OBT) (60d spike in the NW side of tree) #5 11" Tw. W. Oak N31°E 42.55' (60D spike in the SE side of tree) 16" B. Oak S22°E 115.43' (60d spike in the SW side of tree)

Signed by Robert L. Wetherell Date 12-13-93 Surveyor's Michigan License No. 24624

Approved by Peer Review Group December 6, 1993 Robert L. Wetherell, County Representative

