

SURVEY & REMONUMENTATION

MAY 18 1998

LIBER 004 PAGE 0117

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lake _____

Located in: _____ Corner Code # _____

| | | | | | |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 17N | R | 12W | K-4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

REGISTER OF DEEDS
 APR 14 3 04 PM '98
 RECORDED
 LAKE COUNTY, MI.
Registrar H. B. ...

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. Wetherell, in a field survey on Feb. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|---|------------------------------------|--|
| <u>K-4 - 1/4 corner common to Sections 11 & 12, T17N, R12W, Yates Twp., Lake Co., Mi.</u> | | |
| <u>1838 - J. Hodgson, G.L.O.</u> | <u>1974 - R. Griffin, LS 13584</u> | <u>1977 - R.L. Wetherell, LS 24624</u> |
| #1 - 9" W. Oak S52°W 10 Links | L.C.R.C. - L. 02, Pg. 204. | Survey recorded in Liber 02, Pg. 203. |
| #2 - 19" W. Oak N77°E 17 Links | Replaced Iron Pipe with | Witnesses same as Griffin's |
| <u>Undated Co. Survey Records</u> | 5" Square Concrete Monument. | from 1974. |
| Iron Pipe due East 46.8 Links of U.S.F.S. Post. | #3 - 7" W. Oak N62°W 44.55' | |
| | #4 - P. Pole S38°E 51.16' | |
| | #5 - 7" Maple S44°W 65.35' | |
| | #6 - Post West 33.04' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 - 1/4 Corner common to Sections 11 & 12, T17N, R12W, Yates Twp., Lake Co., Mi.

I found Griffin's 5" Concrete Monument in the centerline of a North and South gravel road.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN R. L. W.
 DATE 4-9-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 - 1/4 Corner common to Sections 11 & 12, T17N, R12W, Yates Twp., Lake Co., Mi.

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

10" W. Oak N59°W 44.59' (dock spike in S. side) #3
 P. Pole S39°E 51.14' (Nail and Washer in N.E. side) #4
 10" Maple S50°W 65.17' (dock spike in E. side) #5
 10" R. Oak S72°E 94.06' (60d spike in S. side)

Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date 4-14-98

