

**SURVEY &
REMONUMENTATION**

AUG 31 1999

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

**RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0189**

JUL 23 3 02 PM '99

Shirley H. Richard
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Lake _____	Located in:	Corner Code#	
1. Public Land Survey	<u>T17N</u>	<u>R12W</u>	<u>L-1</u>
	<u>T</u>	<u>R</u>	
	<u>T</u>	<u>R</u>	
	<u>T</u>	<u>R</u>	
2. Property Controlling in Section <u>S</u>	<u>T</u>	<u>R</u>	
<u>S</u>	<u>T</u>	<u>R</u>	
3. Miscellaneous Property in Sec. <u>S</u>	<u>T</u>	<u>R</u>	
<u>S</u>	<u>T</u>	<u>R</u>	
4. Lot No. _____ Recorded Plat			
5. Private Claims _____			

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on January 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

L-1 - N. 1/4 Corner Sec. 1, T17N, R12W

A. Description of original monument and accessories and/or subsequent restoration:

1973 - C. Cole, LS 17615

Section subdivision of Section 1.

Computed position 1/2 distance between Section corners.

Did not set corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set the corner on the Township line at equal distances from the respective Section corners. Distance being 2600.12' each way.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 24" re-bar with Lake County Remon Cap. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

6" B. Oak S12°W 10.95' (60d spike in E. side)

11" Poplar S38°E 17.81' (60d spike in N.E. side)

13" B. Oak S67°W 32.09' (60d spike in side)

3/4" x 24" Capped Iron West 18.84' (S. 1/4 Corner Sec. 36, T18N, R12W)

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345

CHAIRMAN RW

DATE

7-20-99

Date July 21, 1999

Signed by

Robert L. Wetherell

Surveyor's Michigan License No. 24624

