

SURVEY & REMONUMENTATION

JAN 12 1996

COMMISSION

**LAKE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0321

REGISTER OF DEEDS
James H. Deane

SEP 5 3 06 PM '95

RECORDED
LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

Corner in	Lake (County)	Located In:		Corner Code #
		17N	13W	
Public Land Survey		T	R	C-8
		T	R	
		T	R	
		T	R	
Property Controlling in Section	S	T	R	
	S	T	R	
Miscellaneous Property in Sec.	S	T	R	

Lot No. _____, Recorded Plat _____
Private Claims _____

Robert L. Wetherell, August 10, 1995
in a field survey on _____, 19_____,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- C-8 - 1/4 corner common to Sections 19 and 20, T17N, R13W, Pleasant Plains Twp., Lake Co., Mi.
- | | | |
|--|---|--|
| 1838 - John Hodgson, G.L.O.
#1 - 14" Pine N8°W 33 Links
#2 - 12" Pine S60°E 21 Links | 1952 - George Blass, LS 5489
Found large iron bar under surface of blacktop - raised to surface with 1/2" iron rod.
5 - 8" W. Oak N37°E 60.75'
6 - 8" B. Oak N27°W 62.40'
7 - 18" W. oak S9°E 108.90' | 1970 - R.A. Griffin, LS 13584
L.C.R.C. - Liber 02, Pg. 29.
Found 6" x 40" "I" Iron with 1/2" rod over top. Replaced with 5" Square Concrete Monument.
#8 - 6" W. Oak N19°E 68.67'
#6 - 9" B. Oak N31°W 62.75'
#9 - 4" x 7' Post North 33' |
|--|---|--|

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 - 1/4 corner common to Sections 19 and 20, T17N, R13W, Pleasant Plains Twp., Lake Co., Mi.

I found Griffin's 5" square concrete monument 1.5 feet South of the centerline of an East and West blacktop road in monument box. Conditions of the accessories are as follows: #1 gone, #2 Gone, #3 Gone, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 - 1/4 corner common to Sections 19 and 20, T17N, R13W, Pleasant Plains Twp., Lake Co., Mi.

I placed a 3/4" re-bar with Lake county Brass Cap directly over the center of the 5" Square Concrete Monument, and is accepted as a careful and faithful re-establishment of the position of the original corner.

8" W. Oak N22°E 68.65' (Dock Spike in E. side) #8
15" B. Oak N31°W 62.75' (dock spike in W. side) #6
22" W. Oak S8°E 109.45' (60d spike in E. side) #7
7" W. Pine S51°W 100.23' (60d spike in N.W. side)

Signed by *Robert L. Wetherell* Date August 29, 1995
Surveyor's Michigan License No. 24624

