

NOV 15 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0235

For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 13W	C-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED  
LAKE COUNTY, MI.

OCT 7 3 47 PM '94

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert L. Wetherell, in a field survey on June 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11 - (Section corner common to Sections 29, 30 31 & 32, T17N, R13W, Lake Co., Mi.)

- |  |  |
|--|--|
| <u>1838 - John Hodgson, S.D., G.L.O.</u> | <u>1983 - Clinton E. Cole, L.S. 17615</u>        |
| #1 - 18" Black Ash N46°W 28 Links        | Set 1/2" iron rod by double proportionate method |
| #2 - 14" HemLock S20°E 18 Links          | #3 - 22" Maple N22°W 17.4'                       |
|  | #4 - 18" Triple Maple S12°W 25.0'                |
|  | #5 - 5" Ironwood N60°E 19.8'                     |
|  | #6 - Cor. Fence Post S18°E 81.3'                 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 - (Section corner common to Sections 29, 30 31 & 32, T17N, R13W, Lake Co., Mi.)

I found a 1/2" rod that fits Surveyor Cole's accessories reported above. Cole reported the following distances to the respective Section corners used in proportioning.

- West - 4799.84' (G.L.O. computes to be 4785.66')
- South - 5250.54'
- East - 5296.30'
- North - 5249.27'

Condition of accessories are: #1 - Gone, #2 - Gone, #3 - Found in good condition, #4 - Found in good condition, #5 - Found in good condition, #6 - Found in poor condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 - (Section corner common to Sections 29, 30 31 & 32, T17N, R13W, Lake Co., Mi.)

I replaced the 1/2" rod with a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 24" Maple N20°W 18.34' (60d spike in W. side of tree) (#3)
- Triple Maple S24°W 25.63' (60d spike in E. side of tree) (#4)
- 6" Ironwood N60°E 20.01' (60d spike in N.W. side of tree) (#5)
- 24" Maple N82°E 56.49' (60d spike in N. side of tree)

igned by Robert L. Wetherell  
LS 24624

Date October 4, 1994

urveyor's Michigan License No. \_\_\_\_\_

