

FEB 18 1994

LAKE COUNTY REMONUMENTATION

LIBER 003 PAGE 0205  
DEC 13 3 42 PM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Estimote H. Dechow*  
REGISTER OF DEEDS

For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 17 N R 13 W	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Wetherell, in a field survey on November 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 (1/4 Corner Section 32, T17N, R13W, on County Line)

1838 John Mullett, D.S. G.L.O.  
#1 14" Cedar N10°E 18 Links  
#2 12" Cedar N74°W 25 Links

1938 Brue Elliott U.S.F.S. (Jr. Forester)  
Found old cedar stake & set the following  
#3 Pine Post N71°W 0.08 Chains

1983 Clinton E. Cole L.S. 17615: found Elliott's Pine Post and set corner (1/2" rod) using Elliott's bearing and distance from post, and took the following witnesses: #4 18" Maple N79°E 28.65'; #5 8" Maple N15°E 51.20'; #6 10" Maple N67°W 9.44'. He recorded an Act 74 in Liber 2, Page 442 and on November 16, 1985 re-recorded in Liber 3, Page 33.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 (1/4 Corner Section 32, T17N, R13W, on County Line)

I found Surveyor Cole's 1/2" rod and accessories. I also found Elliott's Pine Post. I accepted Cole's 1/2" rod. Corner is 306' more or less East of old railroad grade and 21 feet more or less North of Cedar Creek. Condition of accessories are: #1 Gone, #2 Gone, #3 Found lying down in poor condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 (1/4 Corner Section 32, T17N, R13W, on County Line)

Replaced 1/2" Re-rod with 3/4" x 24" Re-rod with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 20" S. Maple N79°E 28.65' (60d nail in NW side of tree) (#4)
- 10" S. Maple N15°E 51.20' (60d nail in NW side of tree) (#5)
- 12" S. Maple N67°W 9.50' (60d nail in SW side of tree) (#6)
- 22" S. Maple S06°E 55.18' (60d nail in SW side of tree)
- Stake with P.K. Nail 1.1' South

Signed by Robert L. Wetherell Date 12-13-93

Surveyor's Michigan License No. LS 24624  
Approved by Peer Review Group December 6, 1993  
Robert L. Wetherell, County Representative *R.L.W.*

