

SURVEY & REMONUMENTATION

FEB 18 1994

**LAKE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
LAKE COUNTY, MI.
LIBER 003 PAGE 0207
DEC 13 3 42 PM '93

Lucinda H. Dickson
REGISTER OF DEEDS

For corners in SECTION 33

Lake (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>17</u> N R <u>13</u> W	F-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
F-13 (1/4 Corner, Section 33, T17N, R13W, on County Line)

- | | |
|--|---|
| 1838 - John Mullet, G.L.O.
#1 10" Birch N20°W 42 Links
#2 8" B. Ash N33°E 45 Links | 1938 - Bruce Elliott, USFS (Jr. Forester)
Found very old stake and set
#3 Cedar Post S88°E 21 Links |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 (1/4 Corner, Section 33, T17N, R13W, on County Line)

I searched extensively for Elliott's old stake and post, but was unable to recover either. The area of the corner is in a large swamp with severe blow downs. I treated corner as a lost corner and re-set by single proportionate distance.

Distance to Southwest corner - 2641.84'
Distance to Southeast corner - 2641.84'


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 (1/4 Corner, Section 33, T17N, R13W, on County Line)

I set a 3/4" x 24" re-bar with Lake County Brass Cap and accepted as a careful and faithful re-establishment of the position of original corner.

- 4" R. Maple N59°E 10.62' (60d nail in SE side of tree)
- 18" R. Maple S77°E 37.90' (60d nail in North side of tree)
- 16" R. Maple S15°W 35.07' (60d nail in SW side of tree)
- 24" R. Maple N88°W 14.30' (60d nail in NE side of tree)
- 1/2" Re-bar (traverse point) N77°E 168.10'

Signed by Robert L. Wetherell Date 12-13-93
LS 24624



Surveyor's Michigan License No. _____
Approved by Peer Review Group December 6, 1993
Robert L. Wetherell, County Representative R.L.W.