

**SURVEY & REMONUMENTATION**

DEC 14 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in

<u>Lake</u>	Located in:	Corner Code#
1. Public Land Survey	T 17N R 13W	G-3
	T R	
	T R	
	T R	
2. Property Controlling s in Section	T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat		
5. Private Claims		

RECORDED  
LAKE COUNTY, MI  
LIBER 004 PAGE 0225

DEC 9 9 57 AM '99

*Richard Myers*

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on September 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

G-3 - Section corner common to Sections 3, 4, 9 & 10, T17N, R13W, Lake Co., Mi.

**A. Description of original monument and accessories and/or subsequent restoration:**

1838 - J. Hodgson, G.L.O.  
#1 - 10" Pine N18°E 13 Links  
#2 - 8" Pine S28°W 52 Links

1950 - Frank McClung  
Bolt  
#4 - 12" Oak N.E. 17.3'  
#5 - 14" Oak S.E. 37.2'

1977 - Carl Roser, 12028  
Found monument set by G. Shadeo (D.N.R. Surveyor)

1908 - G. West  
"Corner located by R.H. Hollister"  
#3 - 12" B. Oak N9°W 1.14 Chains

1951 - G. Blass, LS 5489  
Found 3/4" Iron Bolt  
#6 - 16" B. Oak S67°W 52.6'  
#4 - 14" B. Oak N75°E 17.15'  
#5 - 12" W. Oak S22°E 37.30'  
#7 - R/W Iron East 33.00'

1996 - R.L. Wetherell, LS 24624  
Survey recorded Liber 04, Pg. 113  
D.N.R. Monument  
#8 - 16" B. Oak S85°W 73.29'  
#9 - 16" B. Oak N3°E 15.71'  
#10 - 16" B. Oak S32°E 57.36'  
#11 - P. Pole S7°E 28.77'

**B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**

I found the D.N.R. concrete monument by Shadko. Corner is 30 feet East of the centerline of road.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found stump N77°E 17.5', #5 Found in good condition, #6 Gone, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition, #10 Found in good condition #11 Found in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I accepted the D.N.R. concrete monument as a substantial monument for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

16" B. Oak S85°W 73.29' (60d spike in S. side) #8  
16" B. Oak N03°E 15.71' (60d spike in W. side) #9  
16" B. Oak S32°E 57.36' (60d spike in N.E. side) #10  
P. Pole S7°E 28.77' (P.K. Nail in E. side) #11

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN R.L.W.  
DATE 10-19-99



Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624