

SURVEYOR'S  
REMONUMENTATION

LAKE COUNTY REMONUMENTATION

RECORDED  
LAKE COUNTY, MI.  
LIBER 003 PAGE 0208

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 13 3 42 PM '93

For corners in  
Lake \_\_\_\_\_  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 17 N R 13 W G-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Lucinda H. DeLeon*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Wetherell, in a field survey on October 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules hereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6-13 - (Section corner common to Sections 33 & 34, T17N, R13W, on County Line)

1838 - John Mullett, D.S., G.L.O.

1938 Bruce Elliott, USFS (Jr. Forester)

#1 24" B. Oak N42°W 32 Links

Found wooden stake for monument

#2 10" W. Pine N49°E 20 Links

#5 Cedar Post S16°E 6 Links (3.96')

1907 - George West, Surveyor

Identified Original Corner

#3 10" W. Pine N49°E 20 Links

#4 13" Tamarack Stump S 48-1/2°W 10 Links

1956 - George Blass, LS 5489

Found rotted wood stake from Surveyor West's witnesses.

Replaced with 1/2" x 18" pipe with two glass bottles.

# 6 6" Elm N10°E 24.94'

# 7 8" Elm N85°E 37.60'

# 8 14" Maple S10°E 31.55'

# 9 12" Maple S22°W 31.82'

#10 USFS Post S10°E 3.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-13 - (Section corner common to Sections 33 & 34, T17N, R13W, on County Line)

I found 1-1/2" Iron Pipe over 1/2" x 18" iron pipe with pieces of broken glass around it. I accepted as the true location. Condition of accessories are: #1 Gone, #2 Found Stump, #3 Found Stump, #4 Gone, #5 Found in good condition, #6 Found Stump, #7 Tree down, #8 Tree down, #9 Found in good condition, #10 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-13 - (Section corner common to Sections 33 & 34, T17N, R13W, on County Line)

Replaced G. Blass 1/2" Iron with 3/4" x 24" Re-rod with Lake County Brass Cap and is accepted as a careful and faithful perpetuation of the position of the original corner.

18" Red Maple S18°W 32.30' (60d nail in SE side of tree)


10" S. Maple N86°W 32.92' (60d nail in South side of tree)

12" S. Maple S71°E 20.90' (60d nail in NE side of tree)

8" S. Maple N22°E 16.73' (60d nail in NW side of tree)

Signed by Robert L. Wetherell Date 12-13-93  
LS 24624

Surveyor's Michigan License No. \_\_\_\_\_



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

Approved by Peer Review Group December 6, 1993  
Robert L. Wetherell, County Representative RLW