

JAN 25 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
 FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in Lake _____ Located in: _____ Corner Code# _____

1. Public Land Survey T 17 N R 13 W I-1
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

RECORDED
 LAKE COUNTY, MI.
 LIBER 004 PAGE 0262
 DEC 8 11 16 AM '00
Shelley M. Meese
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on February 22, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

I-1 - Section corner common to Sections 2 & 3, T17N, R13W - On Twp. Line.

- A. Description of original monument and accessories and/or subsequent restoration:**
- | | | |
|--|--|---|
| 1838 - J. Hodgson, G.L.O.
Set post 15 Links West of post .
#1 - 8" Pine S51°E 76 Links
#2 - 6" Pine S47°W 67 Links | 1940 - C.E. Herman
N.E. corner of the recorded plat of "Lakewoods Acres No. 7"
No. accessories given. Called corner common to Sections 34 & 35, T18N, R13W. | 1993 - R.L. Wetherell, LS 24624
Unrecorded survey in Sec. 2, T17N, R13W.
No accessories given. Shows distance of 2641.49 feet East to N. ¼ corner of Sec. 2. |
| 1930 - G. H. Johnson, Co. Sur.
N.W. corner of the recorded plat of "Lakewoods Acres No. 6".
Called corner common to Sections 34 & 35, T18N, R13W
No accessories given. | 1958 - J.B. Seward, M.S.H.D.
¾" Rod in monument box 0.2' North of centerline of Hwy. U.S. - 10.
#3 - 14" Tw. Oak N38°W 54.94'
#4 - 11" Tw. Oak S20°W 51.86'
#5 - 10" Oak N31°E 48.20' | |

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:
 I found a ¾" pipe in monument box in the centerline of Highway U.S. 10. This iron fits recovered monumentation in the recorded plat of Lakewoods Acres #6 & #7. I found the corner common to Sections 34 & 35, of T18N, R13W, 9.90 feet East.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I accepted the ¾" Pipe in the monument box as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- P. Pole S58°W 71.52' (60d spike S.E. side)
- P. Pole S04°E 68.45' (P.K. nail in W. side)
- 17" W. Oak N1°E 73.96' (60d spike W. side)
- ½" Iron - East 9.90' (Section corner of Sections 34 & 35, T18N, R13W).

NOTIFIED BY THE LAND SURVEYOR REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHRISTOPHER C.W.
 DATE 12-05-2000



Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date December 6, 2000