

JAN 12 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0336

For corners in

Lake (County)	Located In:		Corner Code #/
	17N	13W	
1. Public Land Survey	T	R	I-4
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	R	
	S	R	
3. Miscellaneous Property in Sec.	S	R	
	S	R	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

REGISTERED
 LAKE COUNTY, MI.
 REGISTER OF DEEDS
 OCT 30 2 45 PM '95
 Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4 - 1/4 corner common to Sections 10 and 11, T17N, R13W, Lake Co., Mi.

1838 - John Hodgson, G.L.O.
14" Pine for corner

1960 - George Blass, LS 5489
Making survey for Airport
replaced with Concrete Monument

1972 - Robert Griffin, L.S. 13584
L.C.R.C. - Liber 2, Page 98
Found Blass's Concrete Monument
#3 - 3" B. Oak N60°E 80.88'
#4 - 4" B. Oak S25°E 88.94'
#5 - 5" R. Pine S76°E 76.82'

1951 - George Blass, LS 5489
Found iron pipe
#1 - 4" cherry N42°W 30.53'
#2 - 4" B. Oak S47°E 61.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4 - 1/4 corner common to Sections 10 and 11, T17N, R13W, Lake Co., Mi.

I found a 4" round concrete monument in center of a North and South dirt road and in the center of a seasonal road to the East.

Condition of the accessories are as follows: #1 Gone, #2 Found in good condition, #3 Found in good condition, #4 Found in good condition, #5 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4 - 1/4 corner common to Sections 10 and 11, T17N, R13W, Lake Co., Mi.

I accepted the 4" concrete monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 9" B. Oak N67°E 80.88' (60d spike in S. side) (#3)
- 15" B. Oak S42°E 61.19' (60d spike in S.W. side) (#2)
- 7" B. Oak S18°E 88.82' (dock spike in W. side) (#4)
- 14" B. Oak N28°E 64.59' (60d spike in W. side)

Signed by

Robert L. Wetherell

Date

10-26-95

Surveyor's Michigan License No. _____

24624

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R. L. W.
DATE 10-23-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

