

REMOVED

FEB 18 1994

LAKE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED LAKE COUNTY, MI.

LIBER 003 PAGE 0211

DEC 13 3 43 PM '93

For corners in

Table with columns: Lake (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Signature of Registrar and REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Robert L. Wetherell, in a field survey on October 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: J-13 - (1/4 corner Section 35, T17N, R13W, on the county line)

- 1838 - John Mullett, D.S., G.L.O. #1 10" W. Pine N22°E 77 Links #2 10" W. Pine N80°W 87 Links
1907 - George West, Surveyor Set 1-1/4" Iron Pipe #3 10" B. Oak S29°E 229 Links
1942 - George Blass, LS 5489 Found 1-1/4" Iron Pipe #5 16" B. Oak S52°W 99.20' #6 14" B. Oak N27°E 58.65'
1936 - W.H. Welton, USFS Forester #4 Standard Post North 0.39 Chains
1976 - Robert Griffin, LS 13584 Found 1-1/4" Pipe by G. West #7 10" W. Oak N58°E 67.24' #8 13" B. Oak N21°W 52.83'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 - (1/4 corner Section 35, T17N, R13W, on the county line)

I found 1-1/4" pipe set by George West and later identified by Welton, Blass and Griffin. Accepted as true corner. Condition of accessories are: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Gone, #8 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 - (1/4 corner Section 35, T17N, R13W, on the county line)

Replaced 1-1/4" Iron with 3/4" x 24" re-rod, with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 16" B. Oak N33°E 52.60' (60d nail in SE side of tree)
8" J. Pine S10°W 25.36' (60d nail in East side of tree)
12" B. Oak N21°W 52.83' (10" Dock Spike in NE and tree tag) (#8)
10 Tw. W. Oak S44°E 84.31' (60d nail in NE side of tree)

Signed by Robert L. Wetherell Date 12-13-93

Surveyor's Michigan License No. LS-24624

Approved by Peer Review Group December 6, 1993 Robert L. Wetherell, County Representative

