

FEB 18 1994

LAKE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
LAKE COUNTY, MI  
LIBER 003 PAGE 0212

Dec 13 3 43 PM '93

REGISTER OF DEEDS

For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 17 N R 13 W	K-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on November 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
K-13 - (Section corner common to Sections 35 and 36, T17N, R13W, on the county line)

- 1838 - John Mullett, D.S., G.L.O. #1 18" W. Pine N36-1/2°W 46 Links
- 1857 - Milton Nye, Re-survey #2 4" S. Pine S10°W 106 Links
- 1907 - George West, Surveyor #4 12" B. Oak N55-1/4°W 251 Links
- #3 4" S. Pine S56°E 100 Links
- #5 10 Beech N71°E 255 Links

(SEE OVER FOR CONTINUATION OF "A" - LAND CORNER RECORDATION CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 - (Section corner common to Sections 35 and 36, T17N, R13W, on the county line)


I found 1-1/4" Iron Pipe that was previously used by George Blass and Robert Griffin. Condition of accessories are: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone, #6 Gone, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition, #10 Found in good condition, #11 Found in good condition, #12 Found in good condition, #13 Gone, #14 Gone, #15 Found in good condition, #16 Found in good condition, #17 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 - (Section corner common to Sections 35 and 36, T17N, R13W, on the county line)

Replaced 1-1/4" Iron Pipe with 3/4" x 24" Re-rod with Lake County Brass Cap and is accepted as a faithful and careful re-establishment of the position of the original corner.

- 8" Tw. W. Oak S55°E 50.07' (60d nail in SW side of tree)
- 24" B. Oak N40°W 84.77' (60d nail in NE side of tree) (#7)
- 16" B. Oak S57°W 60.90' (60d nail in NW side of tree) (#8)
- 20" W. Oak N19°W 69.10' (60d nail in NE side of tree)
- USFS Post N45°E 46.95' Tag 8/70



Signed by Robert L. Wetherell Date 12-13-93  
 LS 24624

Surveyor's Michigan License No. \_\_\_\_\_

Approved by Peer Review Group December 6, 1993  
 Robert L. Wetherell, County Representative R.L.W.

CONTINUATION OF "A" - LAND CORNER RECORDATION CERTIFICATE

1936 - W.H. Welton, USFS Technican  
#14 Standard Post N50°E 0.44 Chains

1942- George Blass, LS 5489  
Found 1-1/4" Iron Pipe  
#6 14" Oak S55°E 60.40'  
#7 18" B. Oak N40°W 84.30'  
#8 10" B. Oak S57°W 60.70'

1969 - Robert Griffin, LS 13584  
Found 1-1/4" Pipe  
# 9 Power Pole N40°E 78.85'  
#10 16" B. Oak S15°E 94.00'  
#11 10" B. Oak S57°W 60.70'  
#12 18" B. Oak N40°W 84.30'  
#13 Tele. Pole S45°E 43.32'

UNDATED G.H. JOHNSON, COUNTY SURVEYOR

2 Irons - Well point and 1" Pipe  
#15 12" B. Oak NW 84.3'  
#16 6" B. Oak SW 60.8'  
#17 8" B. Oak SE 60.4'