

NOV 15 1993

COMMISSION LAKE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0177

For corners in Lake

Table with columns: (County), Located In: (T, R), Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REGISTER OF DEEDS

Signature of Register of Deeds

NOV 0 3 40 PM '93

RECORDED LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, Robert L. Wetherell, in a field survey on October 26, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 - Sec. cor., Southwest Cor. Section 31, T17N, R14W)

GLO Resurvey 1856 by Thomas Whelpley
#1 20" W. Pine N66 1/4°W 114 link
#2 40" W. Pine S74°W 229 links
#3 20" W. Pine S48 1/2°E 109 links
#4 10" W. Pine N60°E 100 links

1951 by G. M. Blass, LS 5489
#5 20" B. Oak S08°W (no dist.)
#6 8" W. Oak N64°W 48.12'
#7 12" R. Pine N18°W 79.80'

1971 by R.A. Griffin, LS 13584
#8 5" R. Oak N31°E 72.51'
#9 3" R. Pine S63°E 76.00'
#10 8" W. Oak N60°W 53.65'
#11 4" Sq Oak 7' Pine Post South 1.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 - Sec. cor., Southwest cor. Section 31, T17N, R14W

R. A. Griffin in 1967 found 3/4" x 36" Iron Pipe set by G. M. Blass, replaced Iron Pipe with 5" sq. x 36" Conc. Monu. with brass cap. In 1971 R. A. Griffin with a copy 1856 Re-survey by Thomas Whelpley, was able to locate the true position of the corner by finding three of Whelpleys witnesses, being recovered stumps, #1, #2, & #3 in "A" above. Griffin in the presence of Sam Barnett RLS Moved 1967 Conc. Monu. to the true location of the township corner.

I found Griffin's conc. monu. in it's corrected position, in good condition. Condition of the recorded witnesses is: #1 Gone, #2 Found stump, #3 Gone, #4 Found stump, #5 Gone, #6 Gone, #7 Gone, #8 Found in good condition, #9 Found in good condition, #10 Gone, #11 Found in good condition. North 1/4 Section 1, Town 16 North, Range 15 West is 2658.09' measured by Sam Barnett LS 16923

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 - Sec. cor., Southwest cor. Section 31, T17N, R14W

Accepted R. A. Griffins Concrete Monument with brass cap as a substantial marker for the Section corner, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 8" R. Oak N31°E 72.51' (10" dock spike in NW side of tree) (#8)
6" R. Pine S63°E 76.00' (10" dock spike in NE side of tree) (#9)
8" B. Oak S49°W 52.00' (60d. nail in NW side of tree)
12" R. Pine N18°W 84.45' (60d. nail in NE side of tree)

Signed by Robert L. Wetherell LS 24624

Date 11-5-93

Surveyor's Michigan License No.

Approved by Peer Review Group October 27, 1993
Robert L. Wetherell, County Representative

