

SURVEY & REMONUMENTATION

NOV 15 1993

COMMISSION

LAKE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0180

For corners in LAKE

	(County)	Located In:	Corner Code #:
1. Public Land Survey		T <u>17N</u> R <u>14W</u>	<u>D-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

REGISTERED
 LAKE COUNTY, MI.
 NOV 8 3 40 PM '93
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on October 26, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 (1/4 Corner Section 32, on the county line, T17N, R14W)

GLO Re-survey 1856 by Thomas Whelpley
 #1 12" W. Pine N 34 1/2°W 11 Links
 #2 14" W. Pine S 38 1/2°W 16 Links

1968 by R.A. Griffin, LS 13584
 #3 W. Oak N32°E 73.36'
 #4 4" W. Oak S33°E 63.91'
 #5 5" W. Oak S49°W 72.81'
 #6 6" W. Oak N24°W 68.18'
 #7 4" Sq. x 7' Pine Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 (1/4 Corner Section 32, on the county line, T17N, R14W)

R. A. Griffin in 1968 could not find evidence of either the corner monument or of bearing trees. Griffin re-established the location of corner by single proportional measurement (2636.79' & 2636.70') on a straight line between the S.E. corner and the S.W. corner of Section 32, T17N, R14W. Griffin placed a 5" Sq. x 36" Concrete Monument with brass cap for the corner, (recorded in Liber 01, Page 19). Found Griffin's Concrete Monument in good condition. Condition of recorded witnesses is: #1 Gone; #2 Gone; #3 Found in good condition; #4 Found in good condition; #5 Found in good condition; #6 Found in good condition; #7 Found in good condition.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 (1/4 Corner Section 32, on the county line, T17N, R14W)

Accepted R. A. Griffin's Concrete Monument with brass cap as a substantial marker for the 1/4 corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 8" W. Oak N32°E 73.36' (10" dock spike in N.W. side of tree) (#3)
- 7" W. Oak S33°E 63.91' (10" dock spike in N.E. side of tree) (#4)
- 8" W. Oak S49°W 72.81' (10" dock spike in S.E. side of tree) (#5)
- 9" W. Oak N24°W 68.18' (60d. nail in S.W. side of tree) (#6)
- 4" Sq. x 7' Pine Post 32.97' North (#7)

Signed by Robert L. Wetherell Date 11-5-93
 Surveyor's Michigan License No. LS 24624



Approved by Peer Review Group OCT. 27, 1993
 Robert L. Wetherell, County Representative R.L.W.