

MAY 1 8 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0406

For corners in

Table with columns: Lake (County), Located In: (17N, 14W), Corner Code # (E-4). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

RECORDED LAKE COUNTY, MI. DEC 16 10 26 AM '96 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A black dot is located at the intersection of column E and row 4.

I, Robert L. Wetherell, in a field survey on November 26, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E-4 - 1/4 Corner Common to Sections 8 & 9, T17N R14W, Lake Co., Mi.

- 1838 - John Hodgson, G.L.O. Undated - George Johnson, Co. Sur. 1967 - Robert A. Griffin, LS 13584
#1 - 6" Beech S57°E 19 Links Set Iron (found old stake) L.C.R.C. - Liber 01, Page 23
#2 - 4" Beech N33°W 19 Links #3 - 28" Elm N68-3/4°E 15' Found a 1-1/4" Well pt. and accessory No. 3 dead, but standing.
1908 - J.W. Nicholson, Co. Sur. #4 - P. Pole S56°E 81.13'
#3 - 12" Elm N79°E 23 Links #5 - Gray Boulder S24°E 65.28' ("X" cut in top)
#6 - Gray Boulder S15°E 108.15' ("X" cut in top)
#7 - 4" Post West 33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: E-4 - 1/4 Corner Common to Sections 8 & 9, T17N R14W, Lake Co., Mi.

I found a 5" Square Concrete Monuent badly damaged in the center of North and South Gravel road. In line with fence running East.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition,

RATIFIED BY THE MICHIGAN DEED REVIEW GROUP IN ACCORDANCE WITH P.A. 315 CHAIRMAN R.L.W. DATE 12-12-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 - 1/4 Corner Common to Sections 8 & 9, T17N R14W, Lake Co., Mi.

I replaced the broken 5" Concrete Monument with a 3/4" x 24" re-bar and Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 9" R. Oak N23°E 70.69' (60d spike in W. side)
14" W. Pine S29°E 93.57' (60d spike in N.E. side)
P. Pole S55°E 81.29' (Nail and Washer N.E. side) #4
9" R. Oak S67°W 74.65' (60d spike in S.E. side)
8" W. Pine N60°W 75.74' (60d spike in S.W. side)

Signed by Robert L. Wetherell Date 12-13-1996
Surveyor's Michigan License No. 24624