

**SURVEY & REMONUMENTATION**

NOV 15 1993

COMMISSION

**LAKE COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0182

For corners in LAKE

Located In: Corner Code ##

- |                                       |                         |       |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey                 | T 17N R 14W             | F-13  |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                         |       |
| 5. Private Claims _____               |                         |       |

RECORDED  
LAKE COUNTY, MI.  
NOV 9 3 40 PM '93  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Wetherell, in a field survey on October 25, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-13 (1/4 corner Section 33 on the county line, T17N, R14W)

- GLO Re-survey 1856 by Thomas Whelpley
- #1 5" Pitch Pine S25°W 10 Links
- #2 5" Pitch Pine N27 1/2°E 41 Links

- 1930 by Bruce L. Harden, USFS Technician
- # 3 Cedar Post S88°E 21 Links
- # 4 12" R. Oak S49°W .66 Chains (43.56')
- (Stated corner position doubtful)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 (1/4 corner Section 33 on the county line, T17N, R14W)

Found no remains of previous monuments or accessories. #1, #2, #3 & #4 all gone. I treated this corner as a lost corner and established by single proportional measurement and is on a straight line between controlling corners.

- 2653.38 feet to the S.E. corner Section 33
- 2653.39 feet to the S.W. corner Section 33

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 (1/4 corner Section 33 on the county line, T17N, R14W)

Set 3/4" x 24" Re-rod with brass cap, (Lake County Remonument marker) and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 8" J. Pine N41°W 75.02' (60d. nail in the S.W. side of tree)
- 8" J. Pine S43°W 50.18' (60d. nail in the N.W. side of tree)
- 12" J. Pine N01°E 60.92' (60d. nail in East side of tree)
- 12" R. Pine S17°E 58.36' (60d. nail in the S.W. side of tree)
- Old USFS Pine Post S18°W 22.25'

Signed by Robert L. Wetherell Date 11-5-93

Surveyor's Michigan License No. LS 24624

